

Bill of Quantities (BoQ)/ Schedule (11)
Promoting Usage of Jute Geotechnical Textiles in NER for the State of Manipur under PMGSY works

Earnest Money Deposit (EMD) : 2% of Estimated cost put to tender.

Time Allowed = 1 (one) month

Sl No.	Name of Project	Item of works	Qty.	Unit	Quoted Rate (Rs)		Quoted Amount (Rs.)
					In figure	In words	
1.	Slope Stabilization and protection of soil erosion using jute Geotextile on the road T03 to Lukhambi, in Tamenglong District, 6.60Km. PACKAGE NO. MN07116.	Cost of 500 GSM open weave JGT and installation work over prepared slope, preferably at an angle of internal friction, with proper overlap and anchoring for a stretch of 1815 meter length and 15 meter slope height	28,700.00	Sqm.			

(Handwritten Signature)
 16/11/18