


Bill of Quantities (BoQ)/ Schedule (5)
Promoting Usage of Jute Geotechnical Textiles in NER for the State of Manipur under PMGSY works

Earnest Money Deposit (EMD) : 2% of Estimated cost put to tender.

Time Allowed = 1 (one) month

Sl No.	Name of Project	Item of works	Qty.	Unit	Quoted Rate (Rs)		Quoted Amount (Rs.)
					In figure	In words	
1.	Strengthening of Pavement using Jute Geotextiles in the project Proposed Construction of Roads from "NH-39 to Chajing Karam" Imphal West District under PMGSY-Phase-X 4.40 Km PACKAGE NO. MN0537	Woven Jute Geotextiles for Road construction Cost of Jute Geotextiles, 100 cm wide woven Jute Geotextiles (JGT) 724 gsm (+10%, -5% tolerance)	25,300.00	Sqm.			


 16/2/18